

Sauers Engineering, Inc.

105 Providence Mine Rd., Suite 202
Nevada City, CA 95959
530-265-8021
www.sauerseng.com

To: Planholders
Sierra County Waterworks District No. 1
CALPINE WATER TANK PROJECT

From: Dean Marsh, Project Engineer

Subject: Addendum #1

Date: 07/21/22

This Addendum #1 consists of 1 page. It is the responsibility of the Bidder to assure and guarantee by acknowledging the receipt of this Addendum in the Bid Form, that the Bidder has received the Addendum in its entirety, and that the Bidder accepts all conditions contained herein.

- A. Bid Opening Date:** All references to the bid opening date in the Bid Advertisement, and Instructions to Bidders shall be updated to reflect the new bid opening date. The revised **Bid Opening Date shall be Wednesday August 3rd, 2022 at 2:00 pm.**
- B. Technical Specifications: Section 01-50-00 Temporary Facilities and Controls, 3.A Construction Utilities.** Add the following: Temporary construction water shall be made available to the contractor through the use of a hydrant located within the community. The location of the hydrant and specific procedures for opening the hydrant shall be coordinated with the system operator.
- C. Project Plans, Detail 1/D1-** Delete note requiring all steel for the floor, shell and roof to be A36 1/4" plate. This note was specific to a welded tank and is not applicable to a bolted steel tank.
- D. Project Plans, Detail 7/D2, Check Valve Vault Details-** Due to limitation in availability of materials, precast concrete vault may be "cast-in-place" at contractor's discretion. A cast-in-place structure will require submittal of an engineered design by a California registered civil engineer. Minor variation in proposed dimensions will be considered.

[END of ADDENDUM #1]